
ADDENDUM

Project:	Ft. Branch HVAC Phase 4 7670 S. Eastview Lane Ft. Branch, IN 47648	Addendum No.:	002
		Date:	January 8, 2021
Owner:	South Gibson School Corporation 3321 800 S. Ft. Branch, IN 47648	Project Number:	2011-314
		Contract for:	All


The original specifications and drawings dated December 2020 for the project noted above are amended as noted in this Addendum Number 002. Receipt of this addendum and any subsequent addenda must be acknowledged on the final bid documents. This addendum consists of 1 item(s) and attachment(s).

- 1-1 Labor and Material to disconnect and remove existing light fixtures above Corridor 100. Provide eight 4' LED light fixtures. Surface mount light fixtures in same location as demolished light fixtures. Connect light fixtures to existing light circuit serving light fixtures as was before demolition. Light fixture shall be 48" LED in white housing surface mounted. Fixture color shall be 3500 kelvin, multi-volt range(120-277V), and have a lumen output of 4000. Fixture shall have a wide diffuse lens and accessories to surface mount. Manufacturer and model shall be Lithonia CLX series or equal. Provide dimmer switch above ceiling to control light level of the eight light fixtures. Refer to sheet ADD-02 for additional requirements.

Attachments: Sheet ADD-02


By: Chad Wargel

CC: Tim Armstrong (SGSC), Mike Ruder (SGSC), Chad Wargel (Hafer)



FIRST FLOOR LIGHTING DEMOLITION ADD-02

1/4" = 1'-0"



FIRST FLOOR LIGHTING ADD-02

1/4" = 1'-0"

NOTES:

1. DISCONNECT AND REMOVE POWER FEED TO LIGHT FIXTURE. REMOVE LIGHT FIXTURE. LIGHTING CIRCUIT TO REMAIN FOR REUSE.
2. PROVIDE ALL LABOR AND MATERIAL TO CONNECT LIGHT FIXTURE TO EXISTING LIGHT CIRCUIT AS WAS BEFORE DEMOLITION. FIXTURES SHALL OPERATE WITH TIME SCHEDULE THROUGH BAS SYSTEM IN BUILDING. COORDINATE WITH OWNER TO DETERMINE THE CORRECT SCHEDULE FOR LIGHT FIXTURES TO OPERATE. CONTRACTOR SHALL BE RESPONSIBLE FOR CORRECT OPERATION OF FIXTURES.
3. PROVIDE DIMMER ABOVE CEILING TO CONTROL LIGHT LEVEL OF FIXTURES SHOWN. PROVIDE ALL LABOR AND MATERIAL TO MOUNT DIMMER IN ACCESSIBLE LOCATION. COORDINATE WITH ONSITE MAINTENANCE, JEFF CRECELIUS, FOR EXACT LOCATION.

Ft. Branch Community School
HVAC Upgrades - Phase 4



7670 S Eastview Lane
Fort Branch, IN 47648

HAFER
architects • designers • engineers

21 SE Third Street,
Suite 800
Evansville, IN 47708
T: 812.422.4187
F: 812.421.6776
www.hafersdesign.com

In association with:

Revisions:		
#	Description	Date

Designed By: Drawn By: Checked By:

The drawings, specifications and other documents, including those in electronic form prepared by Hafer for this project are instruments of Service, and may be used solely with respect to this project. The documents may not be reproduced or modified by a third party without first obtaining the express written consent of Hafer. Authorized use of electronic media or file does not guarantee that these files contain complete and accurate information. In order to insure the accuracy of the information contained and that no changes or modifications have been made, these files must be compared to the project's contract documents with stamped and sealed certification and applicable approved modifications.

Sheet title:

LIGHTING PLAN ADD-02

Architect's Project No: Date:

2011-314 December, 2020

Drawing No:

ADD-02